HA. Ihavandhoo Council

Haa Alif Atoll, Republic of Maldives

Bill of Quantities: Harbour Quay Extension

Ref: HC/TND/2026/07

Rates and prices shall be in Maldivian Rufiyaa. Quantities are provisional and subject to remeasurement.

Item	Description	Unit	Qty	Rate (MVR)	Amount (MVR)
1.1	Mobilisation and site setup	LS	1	85,000	85,000
1.2	Demolition of existing damaged apron	m2	220	140	30,800
2.1	Precast concrete piles, 400 x 400 mm	m	360	1,450	522,000
2.2	Reinforced concrete quay beam (C35)	m3	78	6,200	483,600
2.3	Rubber D-type fenders, supply and fix	no	24	3,200	76,800
2.4	Galvanised steel bollards, 30 t	no	8	7,800	62,400
3.1	Compacted coral fill and sub-base	m3	340	320	108,800
3.2	Interlocking concrete block paving	m2	600	420	252,000
3.3	Storm-water drains and gullies	m	95	780	74,100
4.1	Lighting ducts and street light bases	LS	1	64,000	64,000
	Sub-total				1,759,500
	GST (8%)				140,760
	Total bid price				**1,900,260**

Bidders shall fill in unit rates in the Rate column. Amounts shown are the Employer estimate and are for illustration only.

Name and signature of bidder

Date

SAMPLE